

15:135-71100-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1975
11-14-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Sidwell Oil & Gas Co.

Complete Address Box 2475, Pampa, Texas

Lease Name Riese Kandt Well No. 1

Location C SE SE Sec. 33 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4625'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor ~~REXING~~ DNB Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 1 A Day 12 Month 11 Year 1975

The above well was plugged as follows:

RTD 4625' 8 5/8 csg set 248' cwc 160 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/14/75

INV. NO. 2245-W

Signed: L. J. Massey
Well Plugging Supervisor