

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 15 1972  
5-15-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Pickrell Drilling & Southwest Petre-Chem  
Complete Address 705 Fourth National Bank Bldg., Wichita, Kansas  
Lease Name Riese "A" Well No. 1  
Location C NE SE Sec. 33 Twp. 16 Rge. (E) (W) 26  
County Ness Total Depth 4591'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor        Co. Tools         
Address        License No.         
Operation Completed: Hour 11:30 P Day 9 Month 5 Year 1972

The above well was plugged as follows:

RTD 4591' 8 5/8 csg set at 261' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 5-15-72  
INV. NO. 5416-w