



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 9 1962
 11-9-62
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Nov. 2 1962

Dear Sir:

Mr. Raymond Hubbard of R & D Caseing Pulling Co. has this date requested permission to plug the following described well:

Mr. Raymond Hubbard guarantees payment of the plugging fee.

Operator's full Name: Raymond Hubbard
Aylward Drq. Co.

Complete Address: 813 1st Nat'l Bk Bldg.
Wichita 2, Kansas

Lease Name: Stumph-Smith "C" #1 Well No. #1

Location: C NE SE Sec. 17 Twp. 32 Rge. 14 (E) (W) X

County Barber Total Depth 4715' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Raymond Hubbard was instructed to plug the well as follows:

4715' of long string (5 1/2") cemented with 150 sacks cement.

5 1/2" sanded to 4600' and 5 sacks cement. top perforation

at 4630'. 223' of 8 5/8" surface pipe circulated with

cement. Hole filled to 200' with mud, 10' rock bridge and

20 sacks cement. Hole filled to 40' with mud and 10' rock
bridge & 10 sacks cement to base of cellar.

Very truly yours,

Harman Justus
 Conservation Division Agent