

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

MAY 5 - 1966
5-5-66
CONSERVATION DIVISION
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Musgrove of Bowers Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Bowers Drilling Company, Inc.

Complete Address: 1434 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Elsea "A" Well No. # 1

Location: SE SE NE Sec. 15 Twp. 32 Rge. 14 (E)(W) W

County Barber Total Depth 4474' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

880' of 8 5/8" surface pipe, cement circulated with 650 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sacks of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent