

RECEIVED  
KANSAS CORPORATION COMMISSION

11-17

2-040767

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

NOV 29 1994  
11-29-1994  
CONSERVATION DIVISION  
WICHITA, KS

API NUMBER: 15-077-20,891-00-00  
C W/2 SW NW, SECTION 2 TOWNSHIP 33 RANGE 5W

OPERATOR LICENSE # 4511

3300 FEET FROM S SECTION LINE  
4950 FEET FROM E SECTION LINE

OPERATOR WILLIAM H DAVIS  
NAME & 2800 MID CONTINENT TWR  
ADDRESS TULSA OK 74103

LEASE NAME: FORREST #1 *159.58*  
COUNTY: HARPER  
WELL TOTAL DEPTH: 4910' *PB 3801'*

CONDUCTOR PIPE: 4-1/2" @ 4025'

SURFACE CASING: 8-5/8" @ 290'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL X INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: SHEBESTER BECHTEL  
ADDRESS: BLACKWELL OK LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: DARREL RENEAU  
COMPANY NAME: W H DAVIS PHONE: \_\_\_\_\_

WERE: PBTD 3801' - PERFS 3874-78' - CIBP 3801' - 3398' -  
3404' - SAND TO 3350' & 4 SX - 35 SX 900' - 35 SX 600'  
- CIRC 340'

PLUGGING PROPOSAL RECEIVED BY: \_\_\_\_\_

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART ( X ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 1400 DAY: 17 MONTH: 11 YEAR: 1994


ACTUAL PLUGGING REPORT:  
PERFS CLOSED BY PUMPING 100# HULLS, 500# SAND & 5 SX  
CMT DISP TO 2708' - RECOVERED 2700' OF 4-1/2" CSG -  
PULLED CSG AND SPOTED PLUGS @ 908' & 590' - CIRC CMT  
FROM 343' - 0'

REMARKS: ALLIED 60/40 4% GEL

I DID OBSERVE THIS PLUGGING  
**INVOICED**

DATE 12-6-94  
41817

INV. NO. \_\_\_\_\_  
CC: Bill Wix  
Re: Landowner Corp  
11-17

  
Steve Van Gieson (AGENT)