

6 070358

API NUMBER 15-009-23489-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE-SW, SEC. 5, T. 19 S, R. 15 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 6698

Operator: Vicorp Eng Inc
Name: 6200 S. Syracuse
Address: Way ste #125
Englewood, Colorado

_____ feet from S section line

_____ feet from E section line

Lease Name KIBITZER Well # 1

County Barton 119.05

Well Total Depth 3663 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8" feet 1004

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co License Number _____

Address Box 678 North Hwy 281 Great Bend, Mo.

Company to plug at: Hour: 10:00 AM Day: 24 Month: June Year: 19 85

Plugging proposal received from Allen Nicholas

(company name) Nicholas Csg. Pulling (phone) 316-824-6483

were: 8 5/8" 1004 FT S.P. Cui w/ 450 SK cmt, 4 1/2" Cas Set @ 3663 FT
w/ 200 SK cmt, Plug back 3600 FT, Reels @ 3625-28 top.
Plug Bottom 4 SK cmt Sand 3575 FT w/ 4 SK cmt.

Shot Cas (1) Recovered 2583 FT No Previous Problems in Log.
Order 170 SK 50 Formix Gel - 4% CaCl₂ - 15 SK Gel, 5 SK Hulls, 9 8 5/8" Plug, Pump
in with Pump truck Plugging Proposal Received by Marion Schmitt
DOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 PM Day: 24th Month: June Year: 19 85

ACTUAL PLUGGING REPORT Ordered 170 SK 50 Formix 3% CaCl₂, 15 SK Gel,
5 SK Hulls and 8 5/8" Plug, Pumped in 8 5/8" S.P. with
pump truck, Pumped in 8 5/8" ~~with~~, 2 SK Hulls,
5 SK Gel, 1 SK Hulls, 30 SK cmt, 10 SK Gel, 1/2 SK Hulls.
Release Plug, and 140 SK cmt. Max pressure 800 PSI
shut in @ 700 Psig Cemented by Allied Cnt.

Remarks: _____ (if additional description is necessary, use BACK of this form.)

JUL 01 1985

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 7-10-85

INV. NO. 8836

Signed Marion Schmitt
DOIC (TECHNICIAN)