

15-079-20371-0001
drlg. 8-8-1978 R

2 030241

200' 6" 20

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW SE SEC. 23, T 22 S, R 2 W 1/2

330 feet from N/S section line

2510²¹¹⁰ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5621

Lease Name Smith Well # 2

Operator: A.M.I. Inc.

County Harvey 111.64

Name & Address Box 110

Well Total Depth 3435' feet

Moundridge, Ks. 67107

Pipe: Size 5 1/2" feet 3430'

Surface Casing: Size 8 5/8" feet 170'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 5181

Address Box 176, Chase, Ks. 67524

Company to plug at: Hour: 11:00 Day: 23 Month: 4 Year: 19 85

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: P.B.T.D. 3320' Perfor. 2953' to 2966', push plug 3000' sand to 2900' 6% cement, shoot + pull 5 1/2" casg., if high fluid pump 4% hulla, 15% gel, 100% cement down 8 5/8" sur. casg.

RECEIVED STATE CORPORATION COMMISSION

Plugging Proposal Received by Dist #2 Glen Ward (TECHNICIAN)

Plugging Operations attended by Conservation Division Wichita, Kansas All Part None

Operations Completed: Hour: 17:05 Day: 20 Month: 6 Year: 19 85

ACTUAL PLUGGING REPORT Pushed plug 3000', dumped 6% cement / trailer, shot + pulled 1987' 5 1/2" casg. Allied Cementing # 811 pumped 200# hulla, 15% gel, 200# hulla, 100% 60/40 tarmix 2% gel down 8 5/8" sur. casg. Pump Press 300# S.I.P. 100#

Remarks: Top plugging 6-21-85 ck top cement, app. 8' (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-10-85

INV. NO. 8787

Signed Glen Thompson (TECHNICIAN)