

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22/154.000

NEWSNW, Sec. 29, T 17 S, R 23 W/X

195' feet from ~~N/S~~ section line

110' feet from ~~W/X~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5729

Lease Name LUNCH "Y" Well # 5
(Home to the Wind)

Operator: DYNAMAR ENERGY, Inc
Name & Address 4005 E. Kellogg
WICHITA, KS 67218

County NESS

Well Total Depth 4438 feet \$144.23

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 398'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor CLARKE CORPORATION License Number 5105

Address 107 W. FOWLER, MEDICINE LODGE, KS 67104

Company to plug at: Hour: 9:00 AM Day: 7 Month: DEC Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO ELMO MORGANSTERN

(company name) CLARKE (phone) 316-886-5665

were: Sand to 50' above perfs followed w/ 5 sq. cmt. top
at 4150' - Rec. 3237' of 5 1/2" - Pump following sequence
of 3 sq. hells, 20 sq. gel, 70 sq. 50/50 Pozmix, 4% gel-
3% C.C., then 1 sq. hells, 20 sq. gel, release 8 5/8 plug
and finish with 125 sq. cmt.

Signed R. Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00 AM Day: 7 Month: DEC Year: 1982

ACTUAL PLUGGING REPORT Plugged as ordered.
Cementing by Sun.

Remarks: 5 1/2" @ ~~51423'~~ 423' - Perfs @ 4230-32
Max. pressure 750 - S.I. @ 0 without vacuum

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1982
12-14-82
CONSERVATION DIVISION
Wichita, Kansas

Signed R. Barluttan
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 4-4-83

INVOICE NO. 3874-4