

To: 1 071044  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-20,436-0000 27 R  
SW SE SW, SEC. 31, T. 16 S, R. 26 W/E  
330 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131  
Operator: Thunderbird Drilling, Inc.  
Name & Address: P.O. Box 97  
Ellinwood, KS 67526

Lease Name Arnold Well # 4  
County Ness 148.26  
Well Total Depth 4562 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 288

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635  
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 8 Month: 4 Year: 19 92

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

Perfs: 5 1/2" at 4554', Perfs at 4008-20, 4144-58'  
1st plug sand back to 3950' and dump 5 sx cement on top of sand through bailer,  
2nd plug shoot casing at 1220', pump 50 sx cement, 3rd plug shoot casing at 500', pump 50  
sx cement, 4th plug pull casing to 300' and pump 40 sx cement,  
5th plug top off with 10 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 8 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3950' and dumped 5 sx cement on top of sand  
through bailer,  
2nd plug shot casing at 1220' and pumped 50 sx cement,  
3rd plug shot casing at 500' and pumped 50 sx cement,  
4th plug pulled casing to 300' and pumped 40 sx cement,  
5th plug topped off with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 500' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 4-28-92  
INV. NO. 35092

Signed Dan Goodrow  
(TECHNICIAN)

STATE CORPORATION COMMISSION  
RECEIVED  
APR 14 1992  
CONSERVATION DIVISION  
Wichita, Kansas