

7-6 15735-9075-0000

To: 1 070823  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 4/1/64

C SE NE, SEC. 36, T 16 S, R 26 W/E  
3300 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5229

Lease Name Peters Well # A-1

Operator: Phillips Petroleum Company  
Name & Address  
Rt. 3, Box 20-A  
Great Bend, KS 67530

County Ness 146.38

Well Total Depth 4504 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 242

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 6 Month: 7 Year: 1990

Plugging proposal received from Fred Smith

(company name) Phillips Petroleum Company (phone) 316-713-8420

were: 5 1/2" at 4483' Perfs at 4483-4504' Elevation 2569' GL  
1st plug sand back to 4430' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper, plug and pump 175 sx cement.

RECEIVED  
6-17-90  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Mike Spain (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Company: Hour: 2:10 p.m. Day: 6 Month: 7 Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded back to 4430' and dumped 5 sx cement on top of sand through bailer,  
2nd plug pumped 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 175 sx cement down 8 5/8".

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1630' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-17-90

INV. NO. 28610

Signed Dan Godwin (TECHNICIAN)