

To: **1 090414** **3-29**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-20,449.0000
150' NE of C
SE SE, SEC. 34, T 7 16 S, R 26 X
766 feet from S section line
554 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Operator: Pickrell Drilling Company, Inc.
Name & Address 110 N. Market, Ste. 205
Wichita, KS 67202

Lease Name Dumler LM Well # 1
County Ness

Well Total Depth 4555 148.03 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 237

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123

Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 2:10 p.m. Day: 29 Month: 3 Year: 19 94

Plugging proposal received from Ed Mondero

(company name) Pickrell Drilling Company, Inc. (phone) 913-798-2430

Perfs: 5 1/2" at 4524' w/170 sx cement, DVD at 1994' w/340 sx cement, Open hole 4524-55,

Perfs at 4421-23, 4405-4410'

1st plug pump 200 lbs. hulls, 40 sx cement, gel to 2000' and 200 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 p.m. Day: 29 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug hooked onto 5 1/2" casing and pumped in 40 sx cement, 300 lbs.

hulls, 20 sx gel to 2000' and 240 sx cement to surface.

Backside would not take.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this

RECEIVED
STATE CORPORATION COMMISSION
3-31-94
MAR 31 1994

INVOICED
observe this plugging.

Signed [Signature]
CONSERVATION DIVISION
Wichita, Kansas
(TECHNICIAN)

DATE APR 08 1994

INV. NO. 40279

3-29