

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20345-00-00
Spot: CNWNE Sec/Twnshp/Rge: 33-33S-6W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: MADDUX Well Number: 1
County: HARPER Total Vertical Depth: 4547 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 155 N. MARKET, STE 500
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 224 225 SX CMT
Production: Size 4.5 feet: 4547 150 SX CMT
Liner: Size feet:

\$147.78

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/30/2001 12:30 PM

Plug Co. License No.: 6044 Plug Co. Name: STELBAR OIL CORPORATION, INC.

Proposal Rcvd. from: DAVID WILDEROM Company: STELBAR CORP. Phone: (316) 641-0764

Proposed Plugging Method: 35sxs @ 1100'. 35sxs@ 750'. Circulate cement from 275-0'. Perfs. @ 4468-73.

Plugging Proposal Received By: STEVE VANGIESON
Date/Time Plugging Completed: 08/30/2001 12:30 PM

Witness Type: Plugging Operations Partially Witnessed
KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP was set at 4460', and capped with 4sxs of cement. The casing was squeezed at 1200', before plugging of well. The 1100' plug was not needed. The casing was recovered from 1100' and pulled to 734' where 35sxs of cement was spotted. The casing was pulled to 298' where cement was circulated to surface.

RECEIVED
KCC DISTRICT #2


SEP 04 2001
09-04-2001
WICHITA, KS

Remarks: UNITED CEMENTING, 60/40 2% GEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 9-6-01

INV. NO. 2002060355

United Cementing & Acid Company, Inc.100 North Broadway, Suite 3300
Oklahoma City, Oklahoma 73102

(405)-606-8500

15-077-20345-00-00

Plant Location2510 West 6th Street
El Dorado, Kansas 67042
(316) 321-4680**Customer:****Stelbar Oil Corp, Inc.**
155 North Market, Suite 500
Wichita, KS 67202

Invoice No.

3881

Field Ticket

2244

Date

8/31/2001

PO#

Date of Job	County	State	Lease	Well No.
08/30/01	HP	KS	Maddux	#1

Size of Casing	Depth Of Well	Depth Of Job	Plug Depth	Pressure
4-1/2"	4547'	734'		

Quantity	Description	Unit Price	Total
	PLUGGING	UOM	
156 sax.	60/40 Pozmix	sax 4.70	733.20
6 sax.	Gel	sax 9.50	57.00
162 sax.	Bulk charge	sax 0.89	144.18
	Drayage (8.0 tons x .66 x 45 mi.)		237.60
45 mi.	Pump Truck Mileage Charge	mi 2.00	90.00
	Cement Unit		514.95

RECEIVED

RECEIVED
SEP 10 2001
09-10-2001
KCC WICHITA

Thank you for your continued business

Please Remit To:100 North Broadway, Suite 3300
Oklahoma City, Oklahoma 73102

Subtotal	\$1,776.93
Sales Tax	\$ 104.84
Total	\$1,881.77

Terms: Net 30 days From Invoice Date. Please Pay From This Invoice**ORIGINAL INVOICE**