

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21306-00-00 Spot: SESWSW
Sec: 11 Twnshp & Dir: 33 S Rng & Dir: 6 W
Feet: 330 frm N/S: S Feet: 4290 frm E/W: E
Lease/Unit Name: WOLFF B Well Number: 1
County: HARPER Total Vertical Depth: 4550 feet

Operator License No.: 8061

Conductor Pipe: Size feet:

Operator Name: Oil Producers, Inc. of Kansas

Surface Casing: Size 8.625 feet: 264

Address: P.O. BOX 8647
Wichita, KS 67208

Production: Size 5.5 feet: 4549

147.88

6/29

Well Type: GAS

UIC Docket No:

Date/Time to Plug:

Plug Co. License No.: 31925

Plug Co. Name: Quality Well Service, Inc.

Proposal Received from: Richard McIntyre

Company Name: Quality Well Service

OpRepPhoneNo:

Were: PBTD 4531. Perfs, 4362'-65', 4370'-73', 4380'-86', 4423'-26. Sand to 4305', and 5sx of cement. 35sxs@1100'. 35sxs@750'. Circulate cement from 350'-0'

Plugging Proposal Received By: Steve VanGieson

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 06/29/2000 11:00 AM

Actual Plugging Report:

The perf were covered with sand from 4531'-4205' and capped w/5sxs of cement. The casing was recovered from 3618' and pulled to 1100' where 35sxs of cement was spotted. The casing was pulled to 750' where 35sxs of cement was spotted. The casing was pulled to 350' where cement was circulated to surface. The remaining pipe was pulled and the cement was topped off.

RECEIVED
KCC DISTRICT #2

JUL 10 2000
07-10-2000
WICHITA, KS

Remarks: Allied Cement #4444 60/40 4%gel

Anhydrite Plug: No

BottomPlug:

DakotaPlug: No

Plugged through:

I (did / did not) observe this plugging.

Signed

INVOICED

(TECHNICIAN)

DATE 7/19/00

INV. NO. 1060094