

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

2-20

API NUMBER: 15-077-21340-00-00

E/2-NE-SW SECTION 11 TOWNSHIP 33 RANGE 6W

OPERATOR LICENSE # 8061  
OPERATOR Oil Producers Inc. of KS.  
NAME P.O. Box 8647  
ADDRESS Wichita KS. 67208

1980 FEET FROM S SECTION LINE  
2970 FEET FROM E SECTION LINE  
LEASE NAME: WolfFB-3  
COUNTY Harper 148.20  
WELL TOTAL DEPTH: 4560' PBTD 4510'  
PIPE: 4 3/8 @ 4558'  
SURFACE CASING 8 5/8 @ 253'

ABANDONED OIL WELL xx GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: DS & W Well Service  
ADDRESS: Clafin KS. LICENSE: 6901

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: \_\_\_\_\_

PLUGGING PROPOSAL RECEIVED FROM: Kent Strube  
COMPANY NAME: DS&W Well Service PHONE: \_\_\_\_\_  
WERE: Perfs 4371'-4418'  
Sand to 4320' and 4 sks of cement  
35 sks 1100'  
35 sks 700'  
Circulate Cement from 300'-0'

RECEIVED  
KANSAS CORPORATION COMMISSION  
05-01-1998  
MAY 01 1998

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART ( xxx ) NONE ( \_\_\_\_\_ )  
COMPLETED: HOUR: 1630 DAY: 20 MONTH: 2 YEAR: 1998

CONSERVATION DIVISION  
WICHITA, KS

ACTUAL PLUGGING REPORT: The Perfs were covered with sand from 4510'-4320' and capped with 4 sks of Cement. The Pipe was recovered from 3509' and pulled to 1070' where 35 sks of cement was spotted. The pipe was pulled to 695' where cement was spotted. The pipe was pulled to 328' where cement was circulated to surface. The remaining pipe was pulled and the cement was topped off.

REMARKS: Allied Cementing 60/40 4% gel

I DID OBSERVE THIS PLUGGING.

Steve VanGieson  
Steve VanGieson

FORM CP-2/3  
REV. 3/90

INVOICED

DATE 5-4-98

INV. NO. 50407