

7-27

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-077-21,265-00-00
C NE NW, SECTION 11 TOWNSHIP 33 RANGE 6W

OPERATOR LICENSE # 4538 4620 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR BOSWELL ENERGY CORP
NAME & 501 W I-44 STE 300
ADDRESS OKLAHOMA CITY OK 73118

LEASE NAME: CAROTHERS #1
COUNTY: HARPER *163.80*
WELL TOTAL DEPTH: 5040' *PB 4835'*
PIPE: 5-1/2" @ 4835'

SURFACE CASING: 8-5/8" @ 219'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE
ADDRESS: ATTICA KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: JEFF CAPPS
COMPANY NAME: SHAWNEE WELL SERVICE PHONE: _____

WRE: CIBP @ 4320' & 2 SX - 35 SX 1050' - 35 SX 700' - CIRC
CMT 270'-0' - PERFS 4370-76' - 4396-4400'
PBTD 4835'

PLUGGING PROPOSAL RECEIVED BY: STEVE VAN GIESON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 10:30 DAY: 27 MONTH: 7 YEAR: 1994

ACTUAL PLUGGING REPORT:
CIBP SET @ 4320' & CAPPED W/2 SX CMT - 5-1/2" CSG
SHOT LOOSE @ 3006' & PULLED TO 1062' & 35 SX CMT
SPOTTED - CSG PULLED TO 710' & 35 SX CMT SPOTTED - CSG
PULLED TO 280' & CMT CIRC TO SURF

REMARKS: ALLIED CMT #6476

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 9-8-94
SER. NO. 41143

[Signature]
Steve Van Gieson (AGENT)

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 06 1994
09-06-1994
CONSERVATION DIVISION
WICHITA, KS
REV. 3/90