

5-15

2-040881

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: 15-077-21,322-00-00

SE SE NE, SECTION 10 TOWNSHIP 33 RANGE 6W

OPERATOR LICENSE # 8061 2970 FEET FROM S SECTION LINE  
OPERATOR OIL PRODUCERS INC OF KANSAS 330 FEET FROM E SECTION LINE  
NAME & P.O. BOX 8647  
ADDRESS WICHITA, KS 67208

LEASE NAME: CAROTHERS "C" #1  
COUNTY: HARPER 147.88  
WELL TOTAL DEPTH: 4550' PBTD 4425'  
PIPE: 4 1/2" @ 4549'  
SURFACE CASING: 8 5/8" @ 255'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: D S & W WELL SERVICING INC

ADDRESS: CLAFLIN, KS LICENSE: 6901

COMPANY TO PLUG AT: HOUR: DAY: MONTH: YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: KENT STRUBE

COMPANY NAME: D S & W WELL SERVICING INC PHONE: (316) 587-3361

WERE: SAND TO 4345' AND 4 SACKS OF CEMENT  
35 SACKS AT 950'  
35 SACKS AT 625'  
CIRCULATE 300' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: SVG

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( ) PART ( X ) NONE ( )

COMPLETED: HOUR: 12:30 DAY: 15 MONTH: 5 YEAR: 1997

ACTUAL PLUGGING REPORT: THE PERFS WERE COVERED WITH SAND FROM 4425' TO 4345' AND CAPPED WITH 4 SACKS OF CEMENT. CASING PULLED FROM 3720' TO 948' WHERE 35 SACKS OF CEMENT WAS SPOTTED. CASING PULLED TO 624' WHERE 35 SACKS OF CEMENT WAS SPOTTED. CASING WAS PULLED TO 312' WHERE CEMENT WAS CIRCULATED TO SURFACE. REMAINING CASING PULLED AND CEMENT WAS TOPPED OFF.

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENTING

RECEIVED  
KANSAS CORPORATION COMMISSION  
06-05-1997  
JUN 05 1997

I DID OBSERVE THIS PLUGGING.  
*Steve Van Gieson*  
STEVE VAN GIESON  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE JUN 08 1997  
INV. NO. 48298