

2 050631

12-10-87

20839

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13- 077-23,839-00-00

C N/2 NE NE SEC. 2, T 33 S, R 6 W/EX

330 feet from N/2 section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Downing Well # 1

Operator: A. L. Abercrombie

County Harper 155.35

Name &

Address 801 Union Center Bldg.

Well Total Depth 4780 PRTD 4684 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 323

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Kansas

Company to plug at: Hour: Day: 10 Month: 12 Year: 19 87

Plugging proposal received from

(company name) (phone)

were: 5 1/2" casing was set @4741 w/300 sxs cement. Perf. @4352'-56'. Pump 50

sxs on bottom. Pull pipe and squeeze 8 5/8" with 100 sxs cement.

Plugging Proposal Received by Steve VanGieson (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 11:45am Day: 10 Month: 12 Year: 1987

ACTUAL PLUGGING REPORT Pumped 50 sxs 60/40 on bottom plug. Tagged cement next day

@3780'. Shot and pulled 2830' of 5 1/2" casing. Squeezed 8 5/8" with 3 sxs

hulls, 12 sxs gel and 120 sxs 60/40 cement. Max PSI 800# Shutin 500#

RECEIVED STATE CORPORATION COMMISSION

DEC 14 1987 12-14-1987

Remarks: CONSERVATION DIVISION (If additional description is necessary, use BACK of this form.)

I (and others) observe this plugging.

INVOICED

Signed [Signature] (TECHNICIAN)

DATE 12-15-87

INV. NO. 19276