

1060177

TO: STATE CORPORATION COMMISSION

90-12

API NUMBER 15-135-23,207-0000  
C NW SW SEC. 31, T 17 S, R 23 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4620 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME LULA WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY NESS

OPERATOR LICENSE # 8759

WELL TOTAL DEPTH 4470 FEET

OPERATOR: MACK ENERGY CO. PRODUCTION CSG: SIZE 4 1/2" @ 4482' WITH 125 SX

NAME AND ADDRESS PO BOX 400 SURFACE CASING: SIZE 8 5/8" @ 235' WITH 150 SX

DUNCAN, OK 73534

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SWIFT SERVICES INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 08 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) SWIFT SERVICES INC (PHONE) 785-798-2300

WERE: PERFS AT 4374-86 & 4362-64

BOTTOM PLUG AT 4186' WITH CIBP. PERFORATED PIPE AT 813'. COULDN'T PUMP INTO- CHECKED

RECORDS AND HAD BEEN CEMENTED FROM 920' UP. ON 10-12-99 SWABBED CASING TO 1500'. PUT

SWEDGE ON AND FILL CASING. TOOK 100 SX CEMENT. PRESSURED TO 1000# AND SHUT IN.

INVOICED

DATE 10-26-99 PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

TEL NO. 60748

PLUGGING OPERATIONS WITNESSED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 12 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT

BOTTOM PLUG AT 4186' WITH CIBP. PERFORATED PIPE AT 813'. COULDN'T PUMP INTO. CHECKED

RECORDS AND HAD BEEN CEMENTED FROM 920' UP. ON 10-12-99 SWABBED CASING TO 1500'. PUT

SWEDGE ON AND FILL CASING. TOOK 100 SX CEMENT. PRESSURED TO 1000# AND SHUT IN.

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

RECEIVED

I (DID) OBSERVE THIS PLUGGING.

SIGNED Michael J. Maier (TECHNICIAN) OCT 21 1999 WICHITA STATE CORPORATION COMMISSION CONSERVATION DIVISION WICHITA, KANSAS