

1090189

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,604 -0000

NW SW SE, SEC. 31, T 17 S, R 23 W/E
990 feet from N/S section line
2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625
Operator: VAC Petroleum
Name & Address: 6225 East Kellogg
Wichita, KS 67218

Lease Name Horchem Well # 1
County Ness
Well Total Depth 4500 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 395

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829
Address 453 South Webb Road, Wichita, KS 67207

Company to plug at: Hour: 11:00 pm Day: 29 Month: June Year: 19 84

Plugging proposal received from Rex Lutes
(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1710' with 50 sx cement

2nd plug at 960' with 50 sx cement

3rd plug at 450' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by R. Beartuon (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:15 am Day: 30 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1710' with 50 sx cement, 2nd plug at 960' with 50 sx cement, 3rd plug at 450' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 06 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton.

(If additional description is necessary, use BACK of this form)

INVOICED

DATE 7-12-84

INV. NO. 2429

Signed R. Beartuon (TECHNICIAN)