

1 040207

DEC 15 1988

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,528-0000
30' N of
SE NE SW, SEC. 21, T 32 S, R 14 W/EX
1680 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Hoagland Well # 2-21

Operator: Texas Energies, Inc.

County Barber 157.20

Name & Address P.O. Box 947

Well Total Depth 4837 feet

Pratt, KS 67124

Conductor Pipe: Size 13 3/8 feet 39

Surface Casing: Size 8 5/8 feet 973

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 12:30 p.m. Day: 15 Month: 12 Year: 19 88

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 4 1/2" at 4837' PBD 4786' Perfs at 4674-82'

1st plug pump 2 sx hulls and 25 sx Class A cement,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1988

12-21-88

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1 p.m. Day: 15 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 200 lbs. hulls and 25 sx common cement,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3426' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 22 1988 observe this plugging.

Signed Stephen J. Pfeiffer
(TECHNICIAN)

DATE DEC 22 1988

INV. NO. 23453
12-15