

1 090024

9-20

87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-20,300-0000
50' E of
C NW SE, SEC. 16, T 32 S, R 14 W/E
1980 feet from S section line
1830 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Elsea Well # 1

Operator: TXO Production Corporation

County Barber 148.72

Name & Address 1660 Lincoln Street, Suite 1800

Well Total Depth 4576 feet

Denver, CO 80264

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 375

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 20 Month: 9 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4566' Perfs at 4566-76, 4050-56, 4061-68'

1st plug sand back to 4000' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release

8 5/8" wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
9-25-89
SEP 25 1989

Plugging Proposal Received by Steve Durrant

CONSULTANT (TECHNICIAN)
Wichita, Kansas

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 20 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4000' and dump bailed 2 sx cement,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 450 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2300' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 10-2-89

Signed Michael Wilson
(TECHNICIAN)

INV. NO. 25983

9-20