

8-30

1 040158

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-21,936-0000  
C NE NW, SEC. 15, T 32 S, R 14 W/R  
4620 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6769

Lease Name Hinz Well # 1

Operator Name & Address Westmore Drilling Company, Inc.

County Barber 145.93

Address Box 347

Well Total Depth 4490 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well  Gas Well  **RECEIVED**  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation SEP 12 1988 License Number 5105

Address Box 187, Medicine Lodge, KS 67104 9-12-88

Company to plug at: Hour: 9:30 a.m. Day: Wednesday Month: 8 Year: 1988

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4026' PBSD 4026' Perfs at 3942-44'

1st plug sand back to 3900' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour 10:15 a.m. Day: 30 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back from 4026' to 3900' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3000' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 9-15-88 observe this plugging.

INV. NO. 22248

Signed Stephen J. Pfeifer  
(TECHNICIAN)