

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20560-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 15-32S-14W
2200 feet from S Section Line, 350 feet from W Section Line
Lease/Unit Name: ELSEA Well Number: 2
County: BARBER Total Vertical Depth: 4996 feet

Operator License No.: 5506 Conductor Pipe: Size 4.5 feet: 4654
Operator Name: WOOLSEY PETROLEUM CORPOR Surface Casing: Size 8.625 feet: 360
Address: 125 N. MARKET, SUITE 1000 Production: Size feet: 162.37
WICHITA, KS 67202 Liner: Size feet: 10/3

Well Type: GAS UIC Docket No: Date/Time to Plug: 10/03/2000 8:45:00 AM

Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.

Proposal Rcvd. from: ALAN DICK Company: WOOLSEY PETROLEUM Phone: (316) 267-4379

Proposed Plugging Method: DOWN SURFACE CASING PUMP, 300# COTTONSEED HULLS, 10 SX GEL, 50 SX 60/40 POZMIX. 10 SX GEL, 100# COTTONSEED HULLS, 1-8 5/8" WIPER PLUG AND 150 SX SAME CEMENT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/03/2000 9:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 4554-60 & 4484-94. CIBP @ 4420. PERFS AT 4286-91. CIBP @ 4250'. PERFS AT 4032-36. SET CIBP @ 3980' & PUT 2 SX CMT ON TOP OF CIBP. PUMP DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG & 150 SX CMT. MAXIMUM PRESSURE 450#. SHUT IN PRESSURE 300#.

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 2000
10-27-00
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3378' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J Pfeifer
(TECHNICIAN)

INVOICED
DATE 10/30/00 OCT 05 2000
REV. NO. 2001060899