

1 040023

12-9-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,399-0000

NE SW SE, SEC. 12, T 32 S, R 14 W
990 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Brook Well # 1

Operator: Hummon Corporation
Name & Address: 400 One Main Place
Wichita, KS 67202

County Barber 149.08

Well Total Depth 4587 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Elmo Morgenstern - Clarke Corporation License Number 5105

Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 11 a.m. Day: 9 Month: 12 Year: 19 87

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4587' PRTD 4547' Perfs at 4525-27, 4533-35, 4496-99, 4285-86' Elevation 1842' GL

1st plug sand back to 4230' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 5 sx hulls and 125 sx Econolite cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 9 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back from 4547-4230' and put 4 sx cement on top

of sand with dump bailer,

2nd plug pumped down 8 5/8" surface casing with 500 lbs. hulls and 100 sx cement.

Pumping pressure 150-300 psi and shut in 150 psi.

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1987
12-14-87
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used Thrifty Mix cement by B.J. Titan. Recovered 3200' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOLCED

(If desired, observe this plugging.)

DATE 12-15-87

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 19290