

1 030802

5-17-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,116-0000

NE SE NW, SEC. 24, T 16 S, R 26 (W) X

3630 feet from S section line

2970 feet from E section line

Lease Name McKinnis Well # 2

County Ness 148.20

Well Total Depth 4560 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 351

TECHNICIAN'S PLUGGING REPORT

Operator License # 7200

Operator: Scott T. Lutz

Name & Address P.O. Box Drawer D

Shell Knob, MO 65747

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 2 a.m. Day: 17 Month: 5 Year: 19 87

Plugging proposal received from Mike Waggoner

(company name) Red Tiger Drilling Company (phone) 316-263-1201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2010' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,

3rd plug at 375' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6 a.m. Day: 17 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2010' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 375' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAY 22 1987 5-22-87 CONSERVATION DIVISION Wichita, Kansas

Remarks: used 60/40 2% gel 2% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (If not to observe this plugging.)

DATE 5-27-87

Signed Steve Durrant (TECHNICIAN)

INV. NO. 16998

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date April 18, 1987

API Number 15-135-23, 116 0000

OPERATOR: License # 7200
Name Scott T. Lutz
Address P.O. Box Drawer D
City/State/Zip Shell Knob, Mo. 65747
Contact Person H.L. Maddox Scott Lutz
Phone 316-653-4178 417-858-6628

NE. SE. NW 4 Sec. 24. Twp. 16. S, Rg. 26. W
3630 Ft. from South Line of Section
2970 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County Neosho

CONTRACTOR: License # 5302
Name Red Tiger Drilling Co.
City/State Wichita, Kansas

Lease Name McKinnis #2 Well # 2
Ground surface elevation 2583 feet MSL

Well Drilled For: Well Class: Type Equipments:
Oil SWD Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

If OWWO: old well info as follows:

Depth to bottom of fresh water 80
Depth to bottom of usable water 1175

Operator
Well Name
Comp Date Old Total Depth

Surface pipe by Alternate: 1 X
Surface pipe planned to be set 300

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 4-18-87 Signature of Operator or Agent Title Operator

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. 70 yd
This Authorization Expires 10-21-87 Approved By 4-21-87

MOVE IN 58
SPUD 5-9-87

320 8 1/8"

Handwritten signature

Sec. Twp. 16. S, Rg. 26. W

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 2000 feet depth with 50 sxs of 60/40-Pox-Mix-2% Gel
2nd plug @ 1600 feet depth with 50 sxs of
3rd plug @ 900 feet depth with 50 sxs of
4th plug @ 360 feet depth with 40 sxs of
5th plug @ 40 feet depth with 10 sxs of
(2) Rathole with 15 sxs (b) Mousehole with sxs

PUSHER Mike Wagner
TD 4560 FORMATION 1
SURFACE PIPE 8 1/8 @ 357
ANHYDRITE ELEVATION 5-17-87
STARTING TIME & DATE 2:00 AM
COMPLETION TIME & DATE 4:00 AM
1st PLUG @ 2010 FT. W/ 50 SX
2nd PLUG @ 1300 FT. W/ 80 SX
3rd PLUG @ 375 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Allied
TECHNICIAN Durant

60/40 270 gal 2 1/2 cc

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1987
CONSERVATION DIVISION
Wichita, Kansas