

To: 1 080085  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-135-22,901-0000  
SE NW SW, SEC. 24, T 16 S, R 26 W/4  
1650 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 7200  
Operator: Scott T. Lutz  
Name & Address: Drawer D  
Shell Knob, MO 65747

Lease Name Jones Well # 2  
County Ness 149.66  
Well Total Depth 4605 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A   
Other well as hereinafter indicated

Plugging Contractor Halliburton Energy Services License Number  
Address Hays, KS

Company to plug at: Hour: 10 a.m. Day: 15 Month: 11 Year: 19 96

Plugging proposal received from Blu Maddox  
(company name) Halliburton Energy Services (phone)

Work: 5 1/2" at 4603' w/200 sx cement, DV at 2010' w/350 sx cement, CIBP 4484', Perfs at 4442-46'  
1st plug pump 1/4 bbl. cement down 8 5/8" X 5 1/2" annulus,  
2nd plug pump 200 lbs. hulls, 25 sx cement, 24 sx gel, 200 sx cement down 5 1/2" casing.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11 a.m. Day: 15 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped 1/4 bbl. cement down 8 5/8" X 5 1/2" annulus.  
Pressured up to 300 psi.

2nd plug pumped down 5 1/2" casing with 200 lbs. hulls, 25 sx cement, 24 sx gel, and 200 sx cement.  
Maximum pressure 1200 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 8% gel by Halliburton. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-28-96

INV. NO. 47032

Signed Kevin P. Strube (TECHNICIAN)

11-15 JAN 28 1997