

1 050547

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C SW NW, SEC. 24, T 16 S, R 26
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,828-0006
SW NW, SEC. 24, T 16 S, R 26

3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9747

Lease Name Mckinnnis Well # 1-24

Operator: Universal Resources Corp.
Name & Address 1125 17th St Suite 1800
Denver, CO 80202

County Ness 150.15

Well Total Depth 4620 (Mississippi) feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 261

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Corp. License Number 6033

Address 250 N Water, Suite 300 Wichita KS 67202

Company to plug at: Hour: 3:00 pm Day: 4 Month: June Year: 19 85

Plugging proposal received from Terry Mcrae

(company name) Murfin Drilling corp. (phone) 316-267-3241

Instructions: Keep the hole full of drilling mud and spot all plugs through open ended drill pipe.
1st plug at 2000' with 50 sacks of cement. 2nd plug at 1020' with 50 sacks of cement.
3rd plug at 690' with 40 sacks of cement. 4th plug at 300' with 40 sacks of cement. 5th plug
at 40' with a solid bridge and 10 sacks of cement to the surface. Circulate the rat and
mouse holes with 10 sacks of cement each. Use 60/40 pozmix 2% gel 3% cc for all the cement.

The anhydrite top was 1923' Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:00 pm Day: 4 Month: June Year: 19 85

ACTUAL PLUGGING REPORT

Kept hole full of good heavy drilling mud and spotted all plugs through open ended drill pipe. 1st plug at 2000' with 50 sacks of cement. 2nd plug at 1020' with 50 sacks of cement. 3rd plug at 690' with 40 sacks of cement. 4th plug at 300' with 40 sacks of cement. 5th plug at 40' with a solid bridge plug built with 1 sack of hulls and a 8 5/8" wiper plug and then filled hole to surface with 10 sacks of cement. Circulated the rat and mouse holes with 10 sacks of cement each.

Remarks: Halliburton pumped the 60/40 pzmix 2% gel 3% cc cement. (If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
6-7-85
JUN 07 1985

CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey (TECHNICIAN)

INVOICED
DATE 6-18-85
INV. NO. 8561

6-4 JUL 12 1985