

1 050518

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,582-0000

C SE SE SE SEC. 24, T 16 S, R 26 W/E
330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7200

Lease Name Nichepor Well # 1

Operator: Scott T. Lutz

County Ness

Name & Address P. O. Drawer D

Well Total Depth 4560 ^{44.20} feet

Shell Knob, MO 65747.

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 306

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 pm Day: 10 Month: May Year: 19 85

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4560' Perfs at 4521-26' Halliburton FO released and filled 4 1/2" from bottom to 1300'.

Pump 200 sx cement down 4 1/2" casing. If no blow or returns, tie onto 8 5/8" and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 pm Day: 10 Month: May Year: 19 85

ACTUAL PLUGGING REPORT Shot pipe at 1020' and pumped 200 sx cement. Shut in @ 500 psi.

Tied onto 8 5/8" and 4 1/2" annulus and pumped 150 sx cement. Shut in @ 50 psi.

RECEIVED
STATE CORPORATION COMMISSION

MAY 21 1985
5-21-85
CONSERVATION DIVISION

Remarks: No recovery. Used 60/40 Pozmix 2% gel 3% cc Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

Signed Richard W. Lacy
(TECHNICIAN)

DATE 5-21-85

INV. NO. 8210