

1031555

TO: STATE CORPORATION COMMISSION

API NUMBER 15-135-21,577-0002
C NE SE SEC. 23, T 16 S, R 26 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SCHOEPF WELL # 1
COUNTY NESS 149.73

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 6622 WELL TOTAL DEPTH 4607 FEET

OPERATOR: JASON OIL COMPANY PRODUCTION CSG: SIZE 4 1/2" @ 4607' WITH 425 SX

NAME AND PO BOX 701 SURFACE CASING: SIZE 8 5/8" @ 370' WITH 225 SX

ADDRESS RUSSELL, KS 67665-0701

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING COMPANY LICENSE NUMBER NA

ADDRESS PO BOX 31 RUSSELL, KS 67665-0031

COMPANY TO PLUG AT: HOUR: 12:30 PM DAY: 05 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RECEIVED

(COMPANY NAME) ALLIED CEMENTING (PHONE) 785-483-2627 STATE CORPORATION COMMISSION

WERE: PERFS AT 4556-59 & 4566-72

1111 14 2000
7-14-00

PUMP DOWN 4 1/2" 200# HULLS WITH 30 SX CEMENT, 17 SX GEL, & 70 SX CEMENT. MAXIMUM PRESSURE

CONSERVATION DIVISION
Kansas

1100#. SHUT IN WITH 1100#.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:25 PM DAY: 05 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT

PUMP DOWN 4 1/2" 200# HULLS WITH 30 SX CEMENT, 17 SX GEL, & 70 SX CEMENT. MAXIMUM PRESSURE

1100#. SHUT IN WITH 1100#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED
DATE 7/18/00
1060085

SIGNED Steve Durrant
(TECHNICIAN) FORM CP-2/3