

To: 1090281
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S-7

API NUMBER 15- 135-23,744 - 0000

NE SE SW SW, SEC. 23, T. 16 S, R. 26 W/4

530 feet from S section line
4150 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3903

Lease Name Whipple Well # 2

Operator: Mar-Lou Company

County Ness 148.52

Name & Address P.O. Box 218

Well Total Depth 4570 feet

Wilson, KS 67490

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 819, Russell, KS 67665-0819

Company to plug at: Hour: 4 a.m. Day: 7 Month: 5 Year: 19 93

Plugging proposal received from Tom Alm

(company name) Emphasis Oil Operations (phone) 913-483-5345

were: to fill hole with heavy mud and spot cement through drill

1st plug at 2090' with 50 sx cement, 2nd plug at 1190' with 80 sx cement,

3rd plug at 700' with 50 sx cement, 4th plug at 295' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:15 a.m. Day: 7 Month: 5 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 2090' with 50 sx cement,

RECEIVED KANSAS CORPORATION COMMISSION

2nd plug at 1190' with 80 sx cement,

5-12-93 MAY 12 1993

3rd plug at 700' with 50 sx cement,

CONSERVATION DIVISION WICHITA, KS

4th plug at 295' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floreal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 5-14-93

INV. NO. 37700

DISTRICT # SEAT Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date April 17, 1993

Spot NE SE SW SW Sec 23 Twp 16 S. Rg 26 East West

OPERATOR: License # 3903 Name: Mar-Lou Oil Company Address: P. O. Bqx 218 City/State/Zip: Wilson, KS 67490 Contact Person: Marlin E. Robinson Phone: (913) 658-2246

530 feet from South North line of Section 4150 feet from East West line of Section IS SECTION REGULAR IRREGULAR

CONTRACTOR: License # 8241 Name: Emphasis Oil Operations

(NOTE: Locate well on the Section Plat on Reverse Side) County: Ness Lease Name: Whipple Well #: 2 Field Name: Unice East

Well Drilled For: Well Class: Type Equipment: Oil Enh Rec Infield Mud Rotary Gas Storage Pool Ext Air Rotary OWC Disposal Wildcat Cable Seismic # of Holes Other

Is this a Prorated/Spaced Field? yes no Target Formation(s): Mississippi Nearest lease or unit boundary: 530 Ground Surface Elevation: 2622 ft MSL

If OWC: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Water well within one-quarter mile: yes no Public water supply well within one mile: yes no Depth to bottom of fresh water: 100' Depth to bottom of usable water: 1175'

Directional, Deviated or Horizontal wellbore? yes no If yes, true vertical depth: Bottom Hole Location:

Surface Pipe by Alternate: 1 2 Length of Surface Pipe Planned to be set: (240') 200' Length of Conductor pipe required: NA Projected Total Depth: 4600' Formation at Total Depth: Mississippi

Exp. 10/13/93

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq. It is agreed that the following minimum requirements will be met:

1. Notify the appropriate district office before commencing of well.

Pusher SPUD DATE 4-29-93 INIT. LENGTH SURFACE PLANNED 240 RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 1/2" @ 265 CONDUCTOR ANHYDRITE T- B- ELEVATION TD 4570 FORMATION MISS RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 2090 Ft. W/ 50 SX 1/2 Base Anyh. @ 1190 Ft. W/ 80 SX 1/2, 1/2 Plug @ 200 Ft. W/ 50 SX Bottom Surface @ 295 Ft. W/ 50 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN S M DATE 5-6-93 TYPE OF CEMENT 40/40 6% 1/4 F/lostal STARTING TIME 4:00 (AM/PM) DATE 5-7-93 COMPLETION TIME 6:15 (AM/PM) DATE 5-7-93 CEMENT COMPANY Allard