

To: 1 090233 11-13
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,706 - 0500 4912
NW NW SE, SEC. 23, T. 16 S, R. 26 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6622

Operator: Jason Oil Company
Name: Jason Oil Company
Address: P.O. Box 701
Russell, KS 67665

2310 feet from S section line

2310 feet from E section line

Lease Name Schoepf Well # 5

County Ness

Well Total Depth 4575 148.69 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 506, Russell, KS 67665

Company to plug at: Hour: 9:45 p.m. Day: 12 Month: 11 Year: 19 92

Plugging proposal received from Bill Alm

(company name) Emphasis Oil Operations (phone) 913-483-5345

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2042'

1st plug at 2050' with 50 sx cement, 2nd plug at 1180' with 80 sx cement,

3rd plug at 600' with 40 sx cement, 4th plug at 330' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:45 a.m. Day: 13 Month: 11 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2050' with 50 sx cement,

2nd plug at 1180' with 80 sx cement,

3rd plug at 600' with 40 sx cement,

4th plug at 330' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.

(if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

NOV 16 1992

11-16-92

I (State) did not observe this plugging.

Signed [Signature]
(TECHNICIAN)

DATE 12-1-92

INV. NO. 36943

