

1 070144

API NUMBER 15-135-22,943-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE NE SE, SEC. 23, T 16 S, R 26 W/E

1650 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

Lease Name Schoepf Well # 2

Operator: Palomino Petroleum

County Ness

Name & Address P. O. Box 18610

Well Total Depth 4650 151.13 feet

Wichita, KS 67218

Conductor Pipe: Size        feet

Surface Casing: Size 8 5/8 feet 337

Abandoned Oil Well    Gas Well    Input Well    SWD Well    D&A   

Other well as hereinafter indicated       

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 am Day: 28 Month: February Year: 19 86

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4648' PBD 4621' Perfs at 4568-72'

1st plug sand back to 4510' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part        None       

Operations Completed: Hour: 10:15 am Day: 28 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4518' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 900 psi and shut in 100 psi

Remarks: Recovered 3000' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

If (did/did not) observe this plugging.

**NOTICED**

MAR 12 1986

DATE       

STATE CORPORATION COMMISSION Signed Dan Godwin  
(TECHNICIAN)

MAR 11 1986  
3-11-86  
CONSERVATION DIVISION

INV. NO. 12949