

1100374

TO: STATE CORPORATION COMMISSION

API NUMBER 15-135-24'110'6600
C-SE-SW SEC. 22, T 16 S, R 26 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3300 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME PETERS WELL # 1
COUNTY NESS 149.83

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5086 WELL TOTAL DEPTH 4610 FEET

OPERATOR: PINTAIL PETROLEUM, LTD PRODUCTION CSG: SIZE " FEET

NAME AND 225 N. MARKET #300 SURFACE CASING: SIZE 8 5/8" @ 326' WITH SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DISCOVERY DRILLING, INC LICENSE NUMBER 31548

ADDRESS PO BOX 763, HAYS, KS 67601

COMPANY TO PLUG AT: HOUR: 3:00 PM DAY: 12 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM TOM

(COMPANY NAME) DISCOVERY DRILLING, INC (PHONE) 785-623-2920

WERE:

1ST PLUG AT 2090' WITH 50 SX CEMENT, 2ND PLUG AT 1200' WITH 80 SX CEMENT.

3RD PLUG AT 650' WITH 40 SX CEMENT. 4TH PLUG AT 350 WITH 50 SX CEMENT.

5TH PLUG 40'-0 WITH 10 SX. 6TH. CIRCULATE RATHOLE WITH 15 SX. CEMENT. 7TH. PLUG CIRCULATE

MOUSEHOLE WITH 10SX.

 PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 7:00 PM DAY: 12 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2090' WITH 50 SX CEMENT, 2ND PLUG AT 1200' WITH 80 SX CEMENT. 3RD PLUG AT 650

WITH 40 SX CEMENT. 4TH PLUG AT 350 WITH 50 SX CEMENT. 5TH PLUG 40'-0' WITH 10 SX. CEMENT

6TH. PLUG CIRCULATE RATHOLE WITH 15SX. 7TH. CIRC. MOUSE W/10SX CMT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLOW SEAL BY ALLIED CEMENTING

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

INVOICED (SIGNED) Gary Winters/SD
(TECHNICIAN) FORM CP-2/3
DATE 7/18/00
JOB NO. 1060083

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 2000
7-14-00
CONSERVATION DIVISION
Wichita, Kansas

(Circular stamp with initials)