

1 080500

15-007-30161-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 4-1-65
C NE NW, SEC. 11, T 32 S, R 10 W/EX

4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Lease Name Wenzel Well # 1

Operator: Edmiston Oil Co., Inc.
Name & Address 1260 Kansas State Bank Building
Wichita, KS 67202

County Barber 141.99

Well Total Depth 4369 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 244

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 17 Month: March Year: 19 86

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4370' Perfs at 4360-4370'

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 pm Day: 17 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 800 psi and shut in 350 psi

Remarks: Recovered 3505' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 1 1986

INV. NO. 13227

MAR 31 1985
03-31-1985
CONSERVATION DIVISION
Wichita, Kansas

Signed J. H. [Signature]
(TECHNICIAN)