

1 120439

G-27

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,515 - 00-00

NW NW SE, SEC. 10, T 32 S, R 10 W/E

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5993

Lease Name Dohm Well # 1

Operator: KBW Oil & Gas Company

County Barber 145.86

Name:

Address P.O. Box H

Well Total Depth 4488 feet

Bethany, OK 73008

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 294

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 27 Month: 6 Year: 19 90

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4486' cemented w/125 sx, PBD 4460', Perfs at 4372-4407' (2 sets)

1st plug sand back to 4320' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 27 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4320' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement

Pumping pressure 0-1000 psi and shut in 650 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3100' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION JUL 6 1990 06-06-1990 CONSERVATION DIVISION WICHITA, Kansas

INVOICED

observe this plugging.

DATE 7-9-90

Signed [Signature] (TECHNICIAN)

INV. NO. 28552