

080389

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,049-00-00
150' S of
C NW SE, SEC. 6, T 32 S, R 10 W/X
1830 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Dick Well # 2

Operator: Hummon Corporation
Name & Address: 400 One Main Place
Wichita, KS 67202

County Barber (Toronto) 120.90
Well Total Depth 3720 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 229

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Big H Drilling, Inc. License Number 5148
Address 400 One Main Place, Wichita, KS 67202

Company to plug at: Hour: 2:00 am Day: 9 Month: June Year: 19 85

Plugging proposal received from Jerry Tharp

(company name) Big H (phone) 316-263-8521

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 800

1st plug at 800' with 50 sx cement

2nd plug at 275' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by J. A. [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:45 am Day: 9 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 800' with 50 sx cement, 2nd plug at 275' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
06-17-1985
JUN 17 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by BJ-Titan

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

observe this plugging.

Signed J. A. [Signature] (TECHNICIAN)

INVOICED
DATE 6-20-85
INV. NO. 8637
6-9