

To: 1 041248 5-6
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-007-22,462-00-00
NW NW SW, SEC. 7, T 32 S, R 10 W/E
2310 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5050
Operator: Hummon Corporation
Name & Address: 950 N. Tyler Rd.
Wichita, KS 67212-3240

Lease Name Ricke B Twin Well # 1
County Barber 154.38
Well Total Depth 4750 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 3:45 p.m. Day: 6 Month: 5 Year: 19 97
Plugging proposal received from Manny Boatwright
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

work: 5 1/2" at 4573' w/315 sx cement, PBSD 4542', CIBP at 3640', Perfs at 3587-92, 4377-86'
1st plug sand back to 3530' and dump 5 sx cement on top of sand through bailer,
2nd plug spot 50 sx cement at 600',
3rd plug spot 50 sx cement at 280',
4th plug spot 10 sx cement at 40'.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 5 p.m. Day: 6 Month: 5 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 3514' and dumped 5 sx cement on top of sand
bridge through bailer,

Spotted cement plugs through 5 1/2" casing:
2nd plug loaded hole with gel and spotted 50 sx cement at 600',
3rd plug spotted 50 sx cement at 280',
4th plug spotted 20 sx cement at 80'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2415' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (XXXXXX) observe this plugging.

DATE MAY 14 1997

INV. NO. 48110

Signed Stephen J. Pfeifer (TECHNICIAN)