

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 -135-21,873 ^{✓-0000} (of this well)

Operator's Full Name MESSLOWSKI - DEVLIN OIL OPERATIONS

Complete Address 403 INSURANCE BLDG. WICHITA, Kans. 67202

Lease Name BONDURANT Well No. II 1

Location 150'-NW-SE-SE-SW Sec 25 Twp. 16 Rge. 26 (W) W

County NESS Total Depth 4630 ^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated _____

Plugging Contractor WARRIOR DRILLING, INC.

Address 905 CENTRY PLAZA, WICHITA, KS License No. _____

Operation Completed: Hour 6:30 ^{AM} Day 17 Month SEPT Year 1980

The Above well was plugged as follows:

8 5/8" 306 FE SP. CMC w/185ST COMMON 2% GEL. - 3% CA.-CL
ORDERED 115ST 50/50 Permox 6% GEL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

- 1ST PLUG. @ 1230 FE w/70ST CMC.
- 2ND PLUG. @ 300 FE w/25ST CMC.
- 3RD PLUG. -> SOLID BRIDGE MUDS + PLUG. @ 40 FE to 0 w/10ST CMC.
- 5TH IN RAT HOLE

CEMENTED BY ALLIED CMC.

I hereby certify that the above well was plugged as herein stated.

Signed: Murray Schmidt
Well Plugging Supervisor

INVOICED

DATE 9-24-80
INV. NO. 32142

RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1980
CONSERVATION DIVISION
Wichita, Kansas