

KANSAS

Form CP-3  
Rev. 6-4-68STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORTJ. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202API Number 15 -135 - 21503-0000 (of this well)

1-5-79

Operator's Full Name Palomino Petroleum  
Complete Address 500 Insurance Bldg., Wichita, Ks, 67202  
Lease Name Schellenberger Well No. 1  
Location SW SW SE Sec. 29 Twp. 16 Rge. (E) (W) 26  
County Ness Total Depth 4592'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Pipe Pullers, Inc.  
Address Box 486, Ellinwood, Ks. 67526 License No. 462  
Operation Completed: Hour 12:30 P Day 4 Month 1 Year 1979  
The above well was plugged as follows:  
Total Depth 4592' 8 5/8 csg set 325' cwc 200 sk.  
4 1/2 csg set 4580' cw 150 sk cem.  
4 1/2 csg PBTD 4532' with top perf. 4185'.  
Filled 4 1/2 csg W/sd to 4150' -dumped 3 sk cem W/dump bailer. (4150'-4120')  
Cutoff & recovered 97 pcs of 4 1/2 csg. (3029')  
Mixed & pumped down 8 5/8 csg with 20 sk gel & water -followed with 70 sk 50-50 poz  
6% -displaced with 8 sk gel & water -released 8 5/8 cementing pluh & capped with  
70 sk 50-50 poz 6% & shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-5-79INV. NO. 8895-WSigned: Leo M. Mandy  
Well Plugging Supervisor