

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 12 1972  
6-12-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Pickrell Drilling & Southwest Petro-Chem

Complete Address 705 4th Nat'l Bank Bldg., Wichita, Kansas

Lease Name Docner "A" Well No. 1

Location NE NE Sec. 27 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4585'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor        Co. Tools       

Address        License No.       

Operation Completed: Hour 3:15 P Day 11 Month 6 Year 1972

The above well was plugged as follows:

RTD 4585' 8 5/8 csg set at 265' cwc. Cmt. Mat. 50-50 poz cmt W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Murray  
Well Plugging Supervisor

INVOICED  
DATE 6-13-72  
NV. NO. 5861-W