

KANSAS

15735-20963-0000  
Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED  
NOV 11 1974  
11-11-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17017  
Wichita, Kansas 67217

Operator's full Name Pickrell Drilling & Petro-Chem  
Complete Address 405 4th Nat'l Bank Bldg., Wichita, Kansas  
Lease Name McKinnis "B" Well No. 1  
Location C NE NE Sec. 24 Twp. 16 Rge. (E) (W) 26  
County Ness Total Depth 4525'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Co. Tools  
Address        License No.         
Operation Completed: Hour 8:30 A Day 7 Month 11 Year 1974

The above well was plugged as follows:

RTD 4525' 8 5/8 csg set at 211' cwc 150 sk Plg Mat 50-50 poz 6% total gel.  
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 850' thru drill pipe.  
Heavy mud to 215' -set 20 sk cmt plug thru drill pipe. Heavy mud to 40' -set  
solid bridge & 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Z. Massey  
Well Plugging Supervisor

DATE 11/11/74  
INV. NO. 283-W