

15135-21158-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECORDED  
INDEXED

FEB 17 1976  
2-17-76  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Pickrell Drilling Co.

Complete Address 205 Litwin Bldg., Wichita, Kansas

Lease Name Boyd "H" Well No. 1

Location C SW NW Sec. 23 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4587'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor        Co. Tools       

Address        License No.       

Operation Completed: Hour 5:45 A Day 15 Month 2 Year 1976

The above well was plugged as follows:

RTD 4587' 8 5/8 csg set 215' cwc 160 sx. Cmt. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 2-25-76

INV. NO. 2786-W