

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 30 1972  
5-30-72  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address 705 4th Nat'l Bank Bldg., Wichita, Kansas

Lease Name Peters "B" Well No. 1

Location C NW NW Sec. 22 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4590'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 8:15 P Day 25 Month 5 Year 1972

The above well was plugged as follows:

RTD 4590' 8 5/8 csg set at 259' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey  
Well Plugging Supervisor

INVOICED

DATE 5/31/72

INV. NO. 5763-u