

15-007-01120-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

DEC 4 1975
12-04-1975
OFFICE OF THE STATE AGENT
WICHITA, KANSAS

Operator's Full Name Mobil Oil Corp

Complete Address Box 1934 Oklahoma City, OK

Lease Name Nicholas Hrenchir Well No. 1

Location NE/SW/NE Sec. 11 Twp. 32 Rge. 10 (E) (W) W

County Barber Total Depth 4485

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling Co

Address Box 176 Chase, KS License No. 683

Operation Completed: Hour 4:00 PM Day 2 Month 12 Year 1975

The above well was plugged as follows:

238 ft 9 5/8 surface cemented with 250 sacks. 4484 ft 5 1/2 long string
cemented with 200 sacks. Top perf. 4405 ft. Sand to 4350 ft, 5 sacks
cement with bailer. Pulled 3283 ft. 5 1/2. Set 10 ft rock bridge at
240 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12-04-75

INV. NO. 2344-W

Signed: [Signature]
Well Plugging Supervisor