

15-007-10387-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1964
04-21-1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Socony Mobil Oil Co., Inc.

Complete Address: 300 N. Broadway, Wichita, Kansas

Lease Name Fred Zvolanek Unit Well No. # 1

Location C NE NE Sec. 11 Twp. 32 Rge. 10 (E) (W) W

County Harper Total Depth 4455

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 10:00AM Day 18th Month April Year 1964

The Above well was plugged as follows:

239' of 9 5/8" surface pipe, cemented with 250 sacks. 4454' of 5 1/2" long
string, cemented with 200 sacks. Plug back to 4434'. Top perforation
4338'. Bottom of hole was sanded to 4325', and cemented with 5 sacks.
Hole was filled with mud to 250', with 10' of rock, and cemented with
30 sacks. Hole was filled with mud to 40', with 10' of rock, and cement-
ed with 15 sacks to base cellar.

3440' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Ebling
Well Plugging Supervisor

DATE 4/21/64
INV. NO. 8986-W