

15-007-30271-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
DEC 8 1966
12-08-1966
CONSERVATION DIVISION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Faulconer & McCoy

Complete Address: 336 Union Center Bldg., Wichita, Kansas

Lease Name Dohm Well No. # 1

Location C NE SE Sec. 10 Twp. 32 Rge. 10 (E) (W)

County Barber Total Depth 4398'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Hellar Drilling Company, Inc.

Address: 1014 Union Center Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 11:00AM Day 5th Month Dec. Year 1966

The Above well was plugged as follows:

215' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole
was filled with drilling mud to 200', 1st cementing plug, bridged with
1/2 sack of hulls on fluid at 200', and cemented with 25 sacks. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2
sack of hulls on fluid at 40', and cemented with 10 sacks to the base
of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/9/66
INV. NO. 4411-u