

15-007-01589-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 8 1964
07-06-1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Cooperative Refinery Assoc.

Complete Address: 305 Rule Bldg., Wichita, Kansas

Lease Name Dohm Well No. # 1

Location C E/2 NE SE Sec. 10 Twp. 32 Rge. 10 (E) W

County Barber Total Depth 4445

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 12:30 PM Day 5th Month July Year 1964

The Above well was plugged as follows:

219' of 8 5/8" surface pipe, cemented with 175 sacks. 4444' of 5 1/2" long
string, cemented with 50 sacks. Plug back to 4367'. Top perforation
4352'. Bottom of the hole was sanded to 4340', and cemented with 5 sacks.
Hole was filled with mud to 230'. Plug was set at 230', with 10' of rock
bridge, and cemented with 25 sacks, bringing the top of the cement to
160' in the surface pipe. Hole was filled with mud to 40', with 10' of
rock bridge, and cemented with 10 sacks to base of the cellar.
3720' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/6/64
INV. NO. 9408-u

Signed: Archie Elving
Well Plugging Supervisor