


15-007-00340-00-00

CP3



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 22-7

LOCATION SW-2W-SW

SEC. 5 TWP. 28 RGE. N-W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease B. E. Thompson

Operator Continental Oil Co. Address A.F.D. #4 - Lyons - Kans.

Field _____ County Boone

Total Depth 4985 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 20 ft. Circulated with cement
7" casing set at 4575 ft. Cemented with 300 sacks cement.
Plugged back to 4420 ft with cement & chat.
Annular 6 sacks cement at 4420 ft. Ripped off & pulled
the 7" casing - Filled with mud to 210 ft. Set Rock
Bridge & 20 sacks of cement at 210 ft. Mud to
30 ft. Bridge & 10 sacks of cement at the surface.
Shull Casing Pulling Co. - Plugging Contractors

PLUGGED
STATE CORPORATION COMMISSION
FILE NO. 5138-10
BOOK PAGE 25 1950
CONSERVATION DIVISION
Wichita, Kansas

C. H. Steugh
District Conservation Agent

Date 9-13-50

09-25-1950