

15-007-01588-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

CP3

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Barber

Location: NE SW Sec. 3 Twp. 32 Rge. 10 (E) (W) X

Name of Field: _____ Total Depth: 4595

I have this date completed supervision of plugging of:

Lease Name: Rowe Well No. 1

Operator's Full Name: Sinclair Oil & Gas Co.

Complete Address: Box 551, Chase, Kans.

Plugging Contractor: _____

Address: _____ License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 6:30 P.M. Day 4 Month August Year 1958

The above well was plugged as follows:

10 3/4" surface casing set at 274' circulated with cement. Pits were
gunned and hole was filled to 260' with heavy drilling mud. HOWCO cementing
plug set at 260' with 25 sack cement pumped down on plug. Heavy
drilling mud to 40' with HOWCO cementing plug placed with 15 sack
cement to base of cellar.

Signed: _____
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

PLUGGING
FILE SEC 3 T 32 R 10 W
BOOK PAGE 120 LINE 31

08-13-1958