

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

RECEIVED  
STATE CORPORATION COMMISSION

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

AUG - 3 1989

8-3-89

CONSERVATION DIVISION

API NUMBER 007-20,300-0000 (of this well). Wichita, Kansas

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR TXO PRODUCTION CORP. OPERATOR'S LICENSE NO. 5171

ADDRESS 1660 Lincoln St., Suite 1800, Denver, CO PHONE # (303) 861-4246

LEASE (FARM) Elsa WELL NO. 1 WELL LOCATION 1830' FEL COUNTY Barber

SEC. 16 TWP. 32S RGE. 14 ~~(E) (W)~~ TOTAL DEPTH 4576' PLUG BACK TD ---

**Check One:**

OIL WELL --- GAS WELL X D & A --- SWD or INJ WELL --- DOCKET NO. ---

SURFACE CASING SIZE 8 5/8" SET AT 375' CEMENTED WITH 235 SACKS

CASING SIZE 4 1/2" SET AT 4566' CEMENTED WITH 250 SACKS

PERFORATED AT Mississippi O.H.: 4566' to 4576'; Douglas: 4050'-56' & 4061'-68'

CONDITION OF WELL: GOOD X POOR --- CASING LEAK --- JUNK IN HOLE ---

PROPOSED METHOD OF PLUGGING Set CIBP @ - 4200'. Dump bail 2 sxs cmt on top. Fill csg

w/sand to 3900'. Dump bail 2 sxs cmt. Recover  $\pm$  2700' 4 1/2" csg. Plug 8 5/8" w/4 sxs hulls,

25 sxs 60-40 poz-mix w/6% gel, 1 sx hulls, 75 sxs 60-40 poz mix w/6% gel. Cut off & cap 8 5/8"

(If additional space is needed use back of form.) csg.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? --- IS ACO-1 FILED? Yes

(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To be coordinated between KCC & TXO Field

Personnel

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Leamon L. Roberson PHONE # (316) 886-5606

ADDRESS P. O. BOX 125B, Medicine Lodge, Kansas 67104

PLUGGING CONTRACTOR Clarke Corp. LICENSE NO. 5105

107 W. Fowler

ADDRESS P. O. Box 187, Medicine Lodge, KS 67104 PHONE # (316) 886-5665

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Cory West  
(Operator or Agent) Cory West

DATE: 7-31-89

1

State of Kansas



## Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

August 10, 1989

**NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION**

TXO Production Corp.  
1660 Lincoln St., Suite 1800  
Dencer, CO 80264

Elsea 1  
1980' FSL-1830' FEL  
16-21-14W  
Barber County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht  
Director

District: #1 304 W. McArtor

Dodge City, KS. 67801

(316) 225-6760